

Annexure-A

SPECIFICATIONS OF THE ITEMS

A. Walk-In-Tunnels:

BASIC DETAILS OF WALK-IN-TUNNEL	
LENGTH OF TUNNEL	100 FEET
WIDTH OF TUNNEL	12 FEET
SIDE HEIGHT OF TUNNEL	4 FEET
TOTAL HEIGHT OF TUNNEL	7 TO 7.5 FEET
ARC TO ARC SPACING OF TUNNEL AT LENGTH	9 FEET
DRIP IRRIGATION SYSTEM	As Per Design of Tunnel

i. EACH TUNNEL ITEMS				
Sr. No	Item	Details	Unit of Measure	Qty.
1	Main arches GI pipe 1 inch / 16 gauge	To shape as per design	ARCS	12
2	Ms iron bar 3/4 inch	Ms or plain bar with welded washer - 2 feet	NOS.	24
3	Wire stretcher	2 inch /angle iron 2.5 feet long with t shape bar on top	NOS.	2
4	Gi wire pure	12 gauge	Kgs	6
5	Polythene sheet	8 gauge in single layer	Kgs	20
6	Mulching sheet	4 feet	Kgs	3
7	Anti insect net	Complete for tunnel	NOS.	1
8	Installation / bending / Fitting materials	Complete for tunnel	NOS.	1

A. June

A. June

167
167



DIRECTORATE GENERAL AGRICULTURE EXTENSION NEWLY MERGED AREAS,

KHYBER PAKHTUNKHWA, PESHAWAR

Phase-5, Sector B-1, Adjacent NADRA Office, Hayatabad, Peshawar.

Phone No.091-9217721, Food Cell 091-9217717 Fax No.091-9217868 Email: agricfata@yahoo.com


Subject: AMMENDMENT/CORRIGENDUM/CLARITY IN THE TECHNICAL SPECIFICATION OF WALK-IN-TUNNELS TECHNOLOGY UNDER WORLD BANK ASSISTED KP-RIISP (AGRICULTURE COMPONENT) PROJECT.

Memo;

In reference to the bid documents issued against NIT Published in leading Newspapers vide INF (P) 2645/24 regarding the procurement of Walk-in-Tunnels Technology. The following Amendment/Corrigendum/Clarity is made in the technical specification.

S.#	Reference Section	Original text as per Docs	Amended Text	Remarks
1	Annex-A	Main arches gp Pipe 1 Inch/16 Gauge	Main arches GI Pipe 1 Inch/16 Gauge	The gp Pipe is replaced by GI Pipe

The above changes are made for clarity and removal of ambiguity in the technical specifications while submitting bid documents.


DIRECTOR GENERAL
AGRICULTURE EXTENSION
(MDs), PESHAWAR